Residential solar packages

Prices in GHS, excluding VAT/taxes. Equipment and all installation costs included. Transport varies by location.

PACKAGE / SIZE	EQUIPMENT & COMPONENTS	SUPPORTED LOADS / APPLICATION	PRICE (GHS)
1.5kWp	3kW Inverter + 5kWh Battery + 2 × 725W Panels	Lights, TVs, Fans, WiFi, Router, Laptops	35,200.00
3kWp	5kW Inverter + 10kWh Battery + 4 × 725W Panels	One-bedroom home: fridge, TVs, fans, lighting and one 1.5 HP air conditioner (subject to load assessment)	68,400.00
5kWp	6.2kW Inverter + 10kWh Battery + 7 × 725W Panels	Two-bedroom home: fridge, freezer, washing machine, microwave and 2-3 × 1.5 HP air conditioners (subject to load assessment)	87,600.00
7.2kWp	11kW Single Phase + 16kWh Battery + 10 × 725W Panels	2-3-bedroom home: fridge, freezer, washing machine, microwave and 2-3 × 2.0 HP air conditioners (subject to load assessment)	96,000.00
10kWp	11kW Parallel Ready + 16kWh Battery + 14 × 725W Panels	3-4-bedroom home: fridge, freezer, washing machine, microwave and 2-4 × 2.0 HP air conditioners, etc. (subject to load assessment)	118,900.00
12kWp	12kW Single Phase + 2 × 10kWh Batteries + 17 × 725W Panels	5-6-bedroom home: fridge, freezer, washing machine, microwave and 2-4 × 2.0 HP air conditioners, etc. (subject to load assessment)	163,400.00
15kWp	12kW Single Phase + 2 × 16kWh Batteries + 21 × 725W Panels	Items in a 6-bedroom home, villa or guest house (subject to load assessment)	210,000.00
20kWp	20kW Three Phase + 3 × 16kWh Batteries + 28 × 725W Panels	Items in a 7-bedroom home, villa, guest house, apartments, offices, etc. (subject to load assessment)	265,890.00

Transport charges vary within and outside Accra. Final quotations may change after a site visit. Load examples are indicative.

Commercial & industrial

Prices in GHS, excluding VAT/taxes. Equipment and all installation costs included. Transport varies by location.

PACKAGE / SIZE	EQUIPMENT & COMPONENTS	SUPPORTED LOADS / APPLICATION	PRICE (GHS)
20kWp	20kW Inverter + 60kWh Battery Cabinet + 28 Panels	Schools, Offices, Clinics	581,800.00
30kWp	30kW Hybrid + 60kWh Battery Cabinet + 42 Panels	Hotels, Fuel Stations	692,123.00
50kWp	30kW + 20kW Hybrid + HV BESS + 69 Panels	Factories, Warehouses	1,505,665.00
75kWp	3 × 30kW Hybrid + HV Battery System + 104 Panels	Manufacturing Plants	1,895,700.00
100kWp	4 × 30kW Hybrid + HV Battery System + 138 Panels	Industrial Facilities	2,240,900.00
150kWp	5 × 30kW Hybrid + Large HV BESS + 207 Panels	Large Industries	3,395,000.00
200kWp	Multiple 30kW Hybrids + Industrial BESS + 276 Panels	Industrial Parks	5,560,000.00

Transport charges vary within and outside Accra. Final quotations may change after a site visit. Load examples are indicative.

All-in-One solar packages

Prices in GHS, excluding VAT/taxes. Equipment and all installation costs included. Transport varies by location.

PACKAGE / SIZE	EQUIPMENT & COMPONENTS	SUPPORTED LOADS / APPLICATION	PRICE (GHS)
Home Essential	3.5kW All-in-One + 8kWh Battery + 4 × 725W Panels	Lights, TVs, WiFi, Fans, Laptop, 1 Refrigerator	53,500.00
Home Plus	5kW All-in-One + 15kWh Battery + 7 × 725W Panels	Fridge, Freezer, TV, Washing Machine, Microwave, Office Equipment	68,500.00
Home Premium	8kW All-in-One + 16kWh Battery + 10 × 725W Panels	1-2 Air Conditioners, Borehole Pump, Deep Freezer, Large Home	92,500.00
Office Starter	3.5kW All-in-One + 8kWh Battery + 4 × 725W Panels	Small Office (5-10 Staff), Computers, Printer, Router, CCTV	53,500.00
Office Professional	5kW All-in-One + 15kWh Battery + 8 × 725W Panels	Medium Office, Servers, Networking Equipment, Lighting	83,000.00
Business Premium	8kW All-in-One + 16kWh Battery + 12 × 725W Panels	Clinics, Retail Shops, Restaurants, Large Offices	98,500.00

Transport charges vary within and outside Accra. Final quotations may change after a site visit. Load examples are indicative.

Pay Later | Residential

50% upfront; balance over 3 months. Prices exclude VAT/taxes. Installation included; transport varies by location.

PACKAGE, EQUIPMENT & SUPPORTED LOADS	TOTAL (GHS)	50% UPFRONT (GHS)	MONTH 1 (GHS)	MONTH 2 (GHS)	MONTH 3 (GHS)
1.5kWp | 3kW Inverter + 5kWh Battery + 2 × 725W Panels Loads: Lights, TVs, Fans, WiFi, Router, Laptops	45,760.00	22,880.00	7,626.67	7,626.67	7,626.66
3kWp | 5kW Inverter + 10kWh Battery + 4 × 725W Panels Loads: One-bedroom home: fridge, TVs, fans, lighting and one 1.5 HP air conditioner (subject to load assessment)	88,920.00	44,460.00	14,820.00	14,820.00	14,820.00
5kWp | 6.2kW Inverter + 10kWh Battery + 7 × 725W Panels Loads: Two-bedroom home: fridge, freezer, washing machine, microwave and 2-3 × 1.5 HP air conditioners (subject to load assessment)	113,880.00	56,940.00	18,980.00	18,980.00	18,980.00
7.2kWp | 11kW Single Phase + 16kWh Battery + 10 × 725W Panels Loads: 2-3-bedroom home: fridge, freezer, washing machine, microwave and 2-3 × 2.0 HP air conditioners (subject to load assessment)	124,800.00	62,400.00	20,800.00	20,800.00	20,800.00
10kWp | 11kW Parallel Ready + 16kWh Battery + 14 × 725W Panels Loads: 3-4-bedroom home: fridge, freezer, washing machine, microwave and 2-4 × 2.0 HP air conditioners, etc. (subject to load assessment)	154,570.00	77,285.00	25,761.67	25,761.67	25,761.66
12kWp | 12kW Single Phase + 2 × 10kWh Batteries + 17 × 725W Panels Loads: 5-6-bedroom home: fridge, freezer, washing machine, microwave and 2-4 × 2.0 HP air conditioners, etc. (subject to load assessment)	212,420.00	106,210.00	35,403.33	35,403.33	35,403.34
15kWp | 12kW Single Phase + 2 × 16kWh Batteries + 21 × 725W Panels Loads: Items in a 6-bedroom home, villa or guest house (subject to load assessment)	273,000.00	136,500.00	45,500.00	45,500.00	45,500.00
20kWp | 20kW Three Phase + 3 × 16kWh Batteries + 28 × 725W Panels Loads: Items in a 7-bedroom home, villa, guest house, apartments, offices, etc. (subject to load assessment)	345,657.00	172,828.50	57,609.50	57,609.50	57,609.50

Transport rates differ outside Accra and for some locations within Accra. Final quotations may change after a site visit. Interest is included in the package total. The final instalment adjusts for rounding; your agreement confirms payment dates and amounts.

Pay Later | All-in-One

50% upfront; balance over 3 months. Prices exclude VAT/taxes. Installation included; transport varies by location.

PACKAGE, EQUIPMENT & SUPPORTED LOADS	TOTAL (GHS)	50% UPFRONT (GHS)	MONTH 1 (GHS)	MONTH 2 (GHS)	MONTH 3 (GHS)
Home Essential | 3.5kW All-in-One + 8kWh Battery + 4 × 725W Panels Loads: Lights, TVs, WiFi, Fans, Laptop, 1 Refrigerator	69,550.00	34,775.00	11,591.67	11,591.67	11,591.66
Home Plus | 5kW All-in-One + 15kWh Battery + 7 × 725W Panels Loads: Fridge, Freezer, TV, Washing Machine, Microwave, Office Equipment	89,050.00	44,525.00	14,841.67	14,841.67	14,841.66
Home Premium | 8kW All-in-One + 16kWh Battery + 10 × 725W Panels Loads: 1-2 Air Conditioners, Borehole Pump, Deep Freezer, Large Home	120,250.00	60,125.00	20,041.67	20,041.67	20,041.66
Office Starter | 3.5kW All-in-One + 8kWh Battery + 4 × 725W Panels Loads: Small Office (5-10 Staff), Computers, Printer, Router, CCTV	69,550.00	34,775.00	11,591.67	11,591.67	11,591.66
Office Professional | 5kW All-in-One + 15kWh Battery + 8 × 725W Panels Loads: Medium Office, Servers, Networking Equipment, Lighting	107,900.00	53,950.00	17,983.33	17,983.33	17,983.34
Business Premium | 8kW All-in-One + 16kWh Battery + 12 × 725W Panels Loads: Clinics, Retail Shops, Restaurants, Large Offices	128,050.00	64,025.00	21,341.67	21,341.67	21,341.66

Transport rates differ outside Accra and for some locations within Accra. Final quotations may change after a site visit. Interest is included in the package total. The final instalment adjusts for rounding; your agreement confirms payment dates and amounts.

Key terms & choosing your system

A concise guide to payments, eligibility, installation and warranty. Confirm your final quotation and agreement before proceeding.

Pricing conditions
Prices exclude VAT and other applicable taxes. All installation costs are included. Transportation rates vary by location within and outside Accra. Final prices and quotations may change after a site visit.

Payments
Standard: 30% to confirm your invoice, 30% on equipment delivery and 40% after installation. Approved Pay Later: 50% upfront, balance over 3 months; interest is included in the agreed total.

Pay Later eligibility
Age 18+, accepted identification, verified installation location, signed agreement, required deposit and ability to repay. Additional checks may apply. Bank financing through Absa or Stanbic is subject to bank approval.

Installation & warranty
Installation usually takes 1-3 days; larger projects may take up to 2 weeks. Equipment warranty: 5 years; installation: 1 year, both from handover. Approved claims include free service, labour and repairs in year 1; fees apply in years 2-5. Misuse, unauthorised repairs and accidental or intentional damage are excluded; claims are assessed.

Package inclusions
725W High-Efficiency Solar Panels, Hybrid Inverter, Lithium Battery Storage, Mounting Structure, DC & AC Protection, Solar Cables & Connectors, Installation & Commissioning, System Testing, User Training, Warranty Support.

Load guide

3kW System	LED lighting, 1 refrigerator, Television, WiFi router, Laptops, Phone charging, Fans
5kW System	Everything in the 3kW guide, Deep freezer, Washing machine, Microwave, Small water pump, Office equipment
7–10kW System	Everything in the 5kW guide, 1–2 Air Conditioners, Borehole pump, Electric kettle, Security systems, Small office
12–15kW System	Large residential homes, Multiple Air Conditioners, Electric oven, Water heater, Swimming pool pump, Guest house
20kW+ System	Apartment complexes, Hotels, Schools, Commercial buildings, Large offices, Agricultural facilities

Load examples do not mean all appliances can operate together. PV package sizes use kWp; the load guide uses system power in kW.

Next steps: consultation > site assessment > final quotation > agreement > deposit > installation